


# FOOTING LEGEND


- 2-N16x1200 LONG CRACK CONTROL BARS TIED TO UNDERSIDE OF TOP SLAB MESH
- 3-N12x1200 LONG CRANKED CRACK CONTROL BARS TIES TO UNDERSIDE OF TOP SLAB MESH AT SLAB STEP
- 400Φ x 1900 DEEP PIER (BELOW UNDERSIDE OF SLAB), FILL WITH 20MPa CONC. IMMEDIATELY AFTER EXCAVATION. 3-N12 VERT. BARS EVENLY SPACED, 60 COVER. END REQ 60 BELOW TOP OF PIER. FORTECON OVER TOP OF PIER AT UNDERSIDE OF FLOOR SLAB. (BUILDER TO CHECK WITH PLUMBER PRIOR TO CONSTRUCTION TO ENSURE UNDER FLOOR DRAINS WILL FIT AROUND PROPOSED PIER LOCATIONS)
- SAWCUT JOINT. MIN. 30 DEEP WITHIN 12 HOURS OF POUR. STOP REINFORCING 40 SHORT OF JOINT EACH SIDE. FILL WITH NITOSEAL MS400 AFTER 2 WEEKS CURING.



**TOILET SLAB PLAN**  
SCALE 1:50

## SLAB SCHEDULE

MARK	THICKNESS	REINFORCEMENT		CONCRETE STRENGTH	NOTES
		TOP	BOTTOM		
S1	MIN. 130	SL82 (20 COVER)	SL82 (35 COVER)	32MPA	OVER CONTINUOUS FORTECON
S2	MIN. 110	SL82 (40 COVER)	-	32MPA	OVER CONTINUOUS FORTECON



50mm ON ORIGINAL DRAWING - DO NOT SCALE DRAWING

2

SLAB & LINTEL DETAILS ADDED FOR TOILETS

29.10.20

GL

GM

COORDS:

DATUM:

SCALE:

SURVEYED:

SURVEY DATE:

APPROVED / PROJECT LEADER

AMENDMENT / REASON FOR ISSUE

DATE

DES.

DWN.

tonkin

tonkin.com.au

Building exceptional outcomes together

FOR CONSTRUCTION

HABITABLE PLACES ARCHITECTS

PROPOSED UPGRADES TO RAILWAY STATION

MOUNT GAMBIER RAILWAY LANDS

BAY ROAD MOUNT GAMBIER SA

TOILET SLAB PLAN

FILENAME:

JOB NUMBER

SHEET NUMBER


REVISION

20190180WS01-S04-C01REV2.DWG

20190180

S03

2



TOILET LINTEL PLAN

SCALE 1:50

MEMBER SCHEDULE

MARK	MEMBER	NOTES
L1	150x24 FLAT LINTEL	GALVANISED HD 390. 150 LEVEL BEARING EACH END ON SOUND MASONRY. MORTAR PACK OVER TOP OF LINTEL & BELOW ENDS FOR CONTINUOUS BEARING

50mm ON ORIGINAL DRAWING - DO NOT SCALE DRAWING					A3	
					COORDS:	
					DATUM:	
					SCALE:	
					SURVEYED:	
					SURVEY DATE:	
					APPROVED / PROJECT LEADER	
2	SLAB & LINTEL DETAILS ADDED FOR TOILETS	29.10.20	GL	GM		
REV	AMENDMENT / REASON FOR ISSUE	DATE	DES.	DWN.		

tonkin

tonkin.com.au  
Building exceptional outcomes together

FOR CONSTRUCTION

HABITABLE PLACES ARCHITECTS

PROPOSED UPGRADES TO RAILWAY STATION  
MOUNT GAMBIER RAILWAY LANDS  
BAY ROAD MOUNT GAMBIER SA  
TOILET LINTEL PLAN

FILENAME: 20190180WS01-S04-C01REV2.DWG

JOB NUMBER: 20190180

SHEET NUMBER: S04

REVISION: 2